BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
Bruhat Bengaluru Mahanagara Palike

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of Work: Improvements to Roads and Drains at Thindlu colony and Surrounding areas in Ward No. 10 Byatarayanapura.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	577.13	Removing and resetting of footpath slab (Approved arrival rate)	Sqm	235.00	Rupees Two Hundred Thirty Five Only
2	294.35	Earth work excavation by manual means for drains, canals, waste weir, draft, approach channels, key trenches, foundation of Buildings & bridges and such simillar works in all kinds of soils, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work. In all kinds of soils Depth upto 1.5 m	Cum	266.20	Rupees Two Hundred Sixty Six and Twenty Paise Only
3	7.94	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications. Mix 1:3:6 Using 40 mm nominal size graded crushed coarse aggregates	Cum	6587.90	Rupees Six Thousand Five Hundred Eighty Seven and Ninety Paise Only
4	20.52	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications.M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	7650.83	Rupees Seven Thousand Six Hundred Fifty and Eighty Three Paise Only
5	1.53	Steel Fabrication,Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/welding joints, tying with binding wire / soft annealed steel wire and other ancilary operations complete as per drawing and technical specification	Tonne	86912.10	Rupees Eighty Six Thousand Nine Hundred Twelve and Ten Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
6	228.38	Providing and laying 100mm thick pre-cast cover slabs over Road side drains / utility ducts / Rain water harvesting pit of width not exceeding 1000 mm using M20 concrete reinforced with TMT bars Fe 550 @ 6kg/ m2, slabs jointed in CM 1:3 proportion and nicely finished Including providing holes in the Cover slabs wherever necessary for easy drain age of surface water including of labour, materials, scaffolding, usage of machinery, curing, lead and lift charges etc. Complete	Sqm	1287.00	Rupees One Thousand Two Hundred Eighty Seven Only
7	21.00	Providing and fixing 230mm thick pre cast reinforced concrete slab as per design and drawing material cost,transportation, hire charges of machinery complete with all lead and lift conveyance charges labour charges inclusive of cost of all materials(As per data rate)	Sqm	5037.00	Rupees Five Thousand Thirty Seven Only
8	294.35	Unload ing, Loading & Carriage of MaterialsLoading and Unloading of Stone Boulder/Stone aggregates/Sand/Kankar/Moorum. (Tipper 5.5 m3)	Cum	148.50	Rupees One Hundred Forty Eight and Fifty Paise Only
9	376.77	Cost of Haulage Excluding Loading and Unloading,Taking output 10 t load and lead 10 km = 100 t.km	T.Km	198.00	Rupees One Hundred Ninety Eight Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

ಕರಡು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ .....(
ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.

ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಜಿ.ಬಿ.ಎಂ.ಪಿ ಯಲಹಂಕ ವಲಯ
ಬೆಂಗಳೂರು 560092